No.	Items of work	Unit	Rate	Quantity	Cost
					Rs.
	Establishment Tools and plant charges at 18 per cent on the District Board share only, *i.e.*, on half the portion ..	..	..	..	6,466
	Contingencies at 5 per cent	..	..	..	3,570
	Grand Total ..	..	..	..	83,800

S. MUTHUSWAMI IYER,
Executive Engineer.

MEDICAL DEPARTMENT

EPIDEMIC DISEASES HOSPITAL AND LEPER ASYLUM, BANGALORE.

Abstract Notification dated 13th December 1936.

The attention of the public is invited to the detailed notification calling for tenders for the supply of Bedding and Clothing to the Epidemic Diseases Hospital and Leper Asylum, Bangalore, for the year 1936-37, published in pages 2039-2040 of Part VI of the *Mysore Gazette*, dated 17th December 1936.

T. SUBBA RAO,
Medical Officer.

OFFICE OF THE SUPERINTENDENT, MEDICAL STORES, MYSORE GOVERNMENT, BANGALORE.

Absrtact Notification dated 26th November 1936.

The attention of the public in invited to the detailed notification published in pages 2077-2078, of Part VI of the *Mysore Gazette*, dated 24th December 1936, regarding the auction sale of unserviceable articles of the Medical Stores, Bangalore.

M. HIRIYANNAIYA,
Superintendent.

VANI VILAS HOSPITAL, MYSORE.

Abstract Notification.

Notice is hereby given that sealed tenders in triplicate will be received at the Office of the Medical Officer, Vani Vilas Hospital, Mysore, on Monday the 18th January 1937 at 11 A.M. for the supply of Bedding and Clothing for the Vani Vilas Hospital, Mysore, for the year 1936-37. For details, *vide* pages 2040-2041, Part VI of the *Mysore Gazette*, dated 17th December 1936.

M. RATNAMMA ISAAC,
Medical Officer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE CHIEF ELECTRICAL ENGINEER, BANGALORE.

Notice dated 28th December 1936.

1. Sealed tenders in triplicate will be received at the Office of the Chief Electrical Engineer, Bangalore, and the same should be superscribed with name of the work given below.
2. The Plans, detailed estimates and conditions may be obtained at the Office of the undersigned at all working hours.
3. The tenders should be in the form of a statement as given below showing rates in figures.

4. The tenders may be rejected or accepted in full or in part without any reasons being assigned therefor.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Chief Electrical Engineer, Bangalore. No enquiries regarding the acceptance or rejection of a tender will receive any reply. The earnest money of rejected tenders will be returned.

6. Within three days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond failing which his tender will be considered cancelled and the earnest money will be forfeited.

7. The materials to be used should be of the best English or American make and conform to the requirements of the Departmental rules and specifications. Samples should be sent with tenders. When the samples are sent mention should be made of Manufacturers' or Makers' Catalogue.

8. *Name of work*:—Providing electric lights and fans and wiring for three phase power supply to New Automatic Telephone Exchange Bulidings, Bangalore.

9. Last date and time of receiving tender.—15th January 1937. 3 P.M.

10. Time and date of opening tenders in public—3-30 P.M. 15th January 1937.

11. Earnest money required with tender.—Rs. 100.

12. Time for completing the work from date of accepting tender.—Two weeks.

13. Details of the work to be executed as per specification enclosed.

Estimate for providing Electric Lights and wiring for power supply to the New Automatic Telephone Exchange, Bangalore.

Sl. No.	Particulars	Unit	Quantity
1	Supplying No. 191.083 S.W.G. stranded three core lead sheathed, jute served, steel armoured underground cable insulated for 600 volts, and laying 3 feet below the ground covered with 3" river sand all round with pole pipes and junction boxes, etc., complete (for power)	R.ft.	150
2	Do do do No. 6 B. & S. twin conductor lead sheathed, jute-served, steel armoured, under-ground cable for 600 volts, 3 feet below the ground covered with 3" river sand all-round with pole pipes and junction boxes, etc., complete for lighting	R.ft.	150
3	Supplying and fixing a T.W. meter board 4'×3'×4" mounted and wired with one of 100 amp. T.P.S.T. iron clad switch with fuses (for 3 phase power), one of 60 amp. D.P.S.T. iron clad switch with fuses, (main switch for the lighting) and 3 of 15 amp. D.P.S.T. iron-clad switches with fuses—with 3 pilot lamps (2 for power 3 phase, and one for lighting) using 3 lamps of 250 volts, 15 watts, 3 B.C. batten P.B. holders, 3 of 5 amp. bow cut outs and 3 tumbler switches bakelite 5 amp. complete	No.	1
4	Supplying and wiring using No. 14 B. & S. lead covered cable E.C. for lighting outlets	"	39
5	Do do do for controlling switches with 5 amp. bakelite cream reinforced flush type switches mounted in matallic terminal boxes	"	39
6	Do do do for wall plugs using 5 amps. switch combined pattern face entry bakelite cream wall plugs flush type mounted in metallic terminal boxes	"	18
7	Supplying and wiring in $\frac{3}{4}$" Brazed conduit using No. 14 B. & S. insulated wire for 600 volts for lighting outlets imbedding the conduits	"	2
8	Do do do for controlling switches with 5 amp. flush type bakelite cream switches mounted in metallic terminal boxes (imbedding the conduit)	"	2
9	Supplying and wiring for wall plugs (imbedding the conduit) with 5 amp. bakelite cream flush type wall plugs with 5 amp. switches mounted in metallic terminal boxes	"	2
10	Supplying and fixing :—		
	(*a*) 12" trojan fitting with B.C. lamp holder and dull bronze chain complete	"	16
	(*b*) 12" Walton type ceiling fitting with B.C. lamp holder and non-corrosive bakelite ceiling fixture	"	2

Sl. No.	Particulars	Unit	Quantity
	(c) Spherical opal dome 8" with ceiling O.C. fixture and B.C. lamp holder complete	No.	11
	(d) 12" dispersive industrial fitting with B.C. batton lamp holder complete	"	1
	(e) Water tight fitting with B.C. lamp holder	"	1
	(f) White opal shade 9"	"	10
	(g) $\frac{5}{8}$"×9" brass bracket heavy pattern with B.C. lamp holder ..	"	1
	(h) 5 amp. ceiling roses	"	9
	(i) B.C.C.G. lamp holder	"	9
	(j) Flexible cord 6' long	"	4
	(k) Do 25' long with counter weights	"	5
	(l) Lamp M.F.B.C. 220 volts, 150 watts gas filled	"	19
	(m) Do do 100 filled clear	"	11
	(n) Do do 60 do ..	"	11
11	Supplying and wiring from the meter board to two motors of 15 H.P. on porcelain cleats fixed to T.W. batten using No. 4 B.& S. stranded V.I.R. wire for 600 volts	R.ft.	140
12	Masonry, patching and colour washing the lead cable, etc. ..	L. S.	..
13	Grounding the iron clad switches, etc.	L. S.	..
14	Wiring for ceiling fans with No. 14 B. & S. T.C.L.C. cable including fixing regulator with necessary girder clamps, etc., complete ..	No.	2
15	Supplying and fixing ceiling fan 52" sweep 4 blades, 220-volts, 60 cycles with wall type speed regulator, necessary down rods and canopies for fixing the fans	"	2

M. HAYATH,
For *Chief Electrical Engineer*.

OFFICE OF THE SUPERINTENDENT, BANGALORE POWER AND LIGHTING, BANGALORE.

Notice dated 18th December 1936.

1. Sealed tenders in triplicate will be received at the Office of the Superintendent, Bangalore Power and Lighting, Bangalore, and the same should be superscribed with name of the work given below.

2. The Plans, detailed estimates and conditions may be obtained at the Office of the undersigned at all working hours.

3. The tenders should be in the form of a statement as given below showing rates in figures and in words, at which the different items specified will be executed.

4. The tenders may be rejected or accepted in full or in part without any reasons being assigned therefor.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Superintendent, Power and Lighting, Bangalore. No enquirees regarding the acceptance or rejection of a tender will receive any reply. The earnest money of rejected tenders will be returned.

6. Within 3 days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond failing which his tender will be considered cancelled and the earnest money will be forfeited.

7. The materials to be used should be of the best English or American make and conform to the requirements of the Departmental rules and specifications. Samples should be sent with tenders. When the samples are sent mention should be made of Manufacturers' or Makers' Catalogue.

8. Name of work—Wiring for single phase heating and 3 phase power for additional load and realigning the existing wiring as per location of New Transformer centre at Government Porcelain Factory, Bangalore.

9. Last date and time of receiving tender—16th January 1937 at 3-30 P.M.

10. Time and date of opening of tenders in public—4-30 P.M. on 16th January 1937.

11. Earnest money required with tender—Rs. 80.

12. Time for completing the work from date of accepting the tender—Three weeks.

13. Details of the work to be executed—As per specification enclosed.